

रख-रखाव एंव अभियांत्रिकी इकाई
भारतीय कृषि अनुसंधान परिषद
भारतीय कृषि अनुसंधान संस्थान
नई दिल्ली-12.

सं० 156-54/18-19/एमईयू .

दिनांक 06-08-2018

e-निविदा सूचना

निदेशव, भा० कृ० अनु० सं०, की और से एवद्वारा अधोलिखित निविदा कार्य हेतु के० लो० नि० वी०, एम० ई० एस०, रेलवेज, एम० सी० डी०, लोनिवी, या अन्य केंद्र / राज्य सरकार विभाग/ अर्द्ध सरकारी एजेंसीयो के साथ पंजीकृत पाल ठेकेदारो / एजेंसीयो व विशेषकृत एजेंसीयो से मुहरबंद मद दर निविदा आमंत्रित की जाती है । एजेंसीयो के पास वैध पैन, वैट/ टिन तथा GST पंजीकरण सं० होना अनिवार्य है । तथा नीचे निर्देशित कार्यों हेतु विगत दो वर्षों में दो समान कार्यों का अनुभव होना चाहिये ।

| क्र० सं० | कार्य का नाम | अनुमानित लागत | धरोहर राशि | समापन अवधि |
|----------|--|-----------------|--------------|------------|
| 1. | Construction of 3 nos. Speed breaker on street 3 and in campus at IARI, New Delhi-12 | Rs. 3,21,223.00 | Rs. 6,500.00 | 1 |

-निविदा की अंतिम तिथि : 05-09-2018 14.30

-निविदा खुलने की तिथि : 06-09-2018 15.00

निविदा की कीमत : रू० 500/- मात्र (अप्रतिदेय)

इच्छुक एंव पाल एजेंसीया निविदा विवरण को देखने के लिए तथा ई-निविदा प्रस्तुत करने के लिए <http://eprocure.gov.in>

सहायक प्रशासनिक आधिकारी (निर्माण/ एम० ई० यूनिट)

**MAINTENANCE & ENGINEERING UNIT
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE
NEW DELHI-12.**

No. 156-54/18-19ME Unit

Dated : 06-08-2018

e-QUOTATION NOTICE

Item/percentage rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN/VAT/TIN and GST registration number and having experience of two similar nature of works in last two years for the work mentioned below :

| S.N | Name of work | Estimated cost / Item Rate | Earnest Money |
|------------|---|---------------------------------------|--------------------------|
| 1. | Construction of 3 nos. Speed breaker on street 3 and in campus at IARI, New Delhi-12 | Rs. 3,21,223.00 | Rs. 6,500.00 |

Last date & time submission of e-tender processing : up to 14:30 hours of 05.09.18

Opening of e-tender : 15:00 hours of 06.09.18

Desirous and eligible agencies for details & submission to e-tender may visit <http://eprocure.gov.in>

Asstt. Admn. Officer (Works)

No. 156-54/18-19/ME Unit

Name of the work: Construction of 3 nos. Speed breaker on street 3 and in campus at IARI, New Delhi-12.

SCHEDULE OF WORK

| S.N. | Particular | Qty | Unit | Rate | Amount |
|------|--|----------|------|---------------|------------------------|
| 1. | P/L Cold mixed bitemestic ready made concrete with stone chipping (60 % with 6.00 mm 40% with 10 mm nominal size) @ 56 kg per cum or more of cold bitemun of stone chipping and 128 kg / Cum of sand over cold straigst bitumen i/c consolidation with Road roller of 8 to 10 tuns with 100 mm at centre hight of the road, 80 mm, 60 mm, 40mm, 20 mm, and 0mm at a distance of 500 mm on either site respectively including necessary straight bitumun to make a Speed Breaker on the road as per the direction of Engineer-In-charge. | 15000.00 | kg | 17.25 | 258750.00 |
| 2. | Manufacturing supplying and fixing retro reflective sign boards equilateral triangleof size 850 x 850 x 850 mm made up of 2 mm thick M.S. sheet, face to be fully covered with retro reflective / non –reflecting sheeting in red for border and white for background or other colour combination including subject matter, massage (bi-lingual) (Hindi & English), symbols and borders etc., pasted on substrate by an adhesive backing, back support frame of M. S. Square tube of Size 30 x 30 x 4 mm of all three sides at the back of M. S. sheet along with 01 nos. M.S. Square tube having length upto 2.71 metre of size 49.5 x 49.5 x 4.5 mm to a vertical post welded with holdfast at base of same size 150 mm long excluding P/ fixing M. S. message plate of 2 mm thick of size 300 x 850 mm, steel work to be painted with two painted with two or more coats of synthetic enamel paint of required shade and of approved brand & backside of aluminum sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat complete as drawing, specification and direction of Engineer-In-Charge. | 06 | each | 6000.00 | 36000.00 |
| 3. | Painting road surface marking with adequate nos of coats to give uniform finish with ready mixed road marking paint conforming to IS : 164, on bituminous surface in white/yellow shade, including cleaning the surface of all dirt, scales, oil, grease and foreign material etc. complete. | | | | |
| | New work (Two or more coats) | 120.00 | sqm | 133.10 | 15972.00 |
| 4. | Providing and fixing Glow studs of size 100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acryloretrite) or HIP (High impact polystyrene) or ABS having electronically welded micro- prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro- reflective surface shall be 35 (+/-5) degress to base .The reflective panels on both sides with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4 : 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge | 66.00 | each | 159.10 | 10501.00 |
| | | | | Total= | Rs. 3,21,223.00 |

Subject to the following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within 7 days from the date of award and complete within one month failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. GST will be paid extra as per norms of the Ministry of Finance.
6. All the material, laboures, T & P etc. required will be arranged by the firms itself.
7. The agency shall deposit security @ 5% of the sanctioned amount including EMD.
8. Any other item to be required at site to complete the work be executed as per lowest quitted rates.on DSR-2016.
9. The rates quoted shall remain valid for 180 days from the date of opening of quotations/tenders.
10. A running payment may be made of the successful completion of work for 1/2nd or more amount of work.
11. The Director, IARI has the right to reject any or all the quotations/tenders without assigning any reason.

Percentage rate to be quoted above or below in figure:

In words:

Name & Signature of the Agency:-.....

(VIKAS KUMAR)
Juniar Engineer/ T-3

(Er. CHARAN SINGH)
Asstt. Chief Tech. Officer (Civil), ME Unit